

## HENRY MOORE

Working in close consultation with the Royal Parks PAYE were appointed to undertake the work needed to return the Arch to its former prominent position on the north bank of the Serpentine facing Kensington Palace. The seven individual pieces of travertine that form the sculpture weigh a total of 37 tonnes and each had to be carefully cleaned and repaired using carefully sourced matching material.

In order to overcome the previous structural issues that had caused the original instability, a new internal skeleton of stainless steel dowels and Cintec anchors has been drilled in. Drill holes have been plugged with discs of travertine to provide a seamless finish.